

TEST REPORT

Test Report No. : 11 0528  
Date : 27.10.2021  
Page No. : 1 of 19  
Location of Testing : SCIENTIFIC AND INDUSTRIAL TESTING AND  
RESEARCH CENTRE (Si'Tarc)  
83 & 84, Avarampalayam Road, K R Puram Post  
COIMBATORE – 641 006.  
Name and Address of the Customer : Tag Solar System LLP  
D 54 Subhash Marg, Chomu House, C-Scheme,  
Jaipur- 302 001.  
Customer Doc. Ref. No. & Date : CH013, 12.10.2021  
Item Description : 2.2kW/ 3.0 HP Universal Solar Pump Controller  
Sample Identification Details  
Grade/Variety/Type/Size/Class. : Model: KISAN UNIVERSAL 3HP  
Batch No./Date of Manuf./Brand : S. No. 1020\_4030\_000847  
Item Received on : 19.10.2021  
Sample Drawn By : Customer  
Seal/Signature/QR Code No. : -  
Any Other Information : Test as per Ministry of New and Renewable Energy  
Testing Procedure for Universal Solar Pump Controller  
(USPC) Annexure-iii of circular no. F. No. 41/3/2018-spv  
division dated 17.7.2019.

Tests Authorised By



D.ANGURAJ  
Electrical Testing Laboratory

----- For SITARC Office use only -----

Si'Tarc Invoice No. & Date : Invoice No. 1464/21-22, dated 27.10.2021

M/s Tag Solar System LLP  
D 54 Subhash Marg, Chomu House, C-Scheme,  
Jaipur- 302 001.


Always look up for HOLOGRAM on each pages of this report to confirm genuine Test Report.

Report Issued By

Approved By

  
R.JEYABHARATHI  
Manager (Customer Care)



  
Dr.K.ULAGANATHAN  
Director.

Note : This Report is Subjected to the Terms and Conditions Mentioned Overleaf.

**TEST REPORT FOR UNIVERSAL SOLAR PUMP CONTROLLER**

**MINISTRY OF NEW AND RENEWABLE ENERGY**

**UNIVERSAL SOLAR PUMP CONTROLLER (USPC) SPECIFICATIONS FOR STAND-ALONE APPLICATIONS**

**Annexure-III of Circular No. F. No. 41/3/2018-SPV Division dated 17.7.2019**


**1.0 DETAILS OF THE SAMPLE**

|   |  |             |          |                     |                  |
|---|--|-------------|----------|---------------------|------------------|
| Name of the Sample  | UNIVERSAL SOLAR PUMP CONTROLLER (USPC) |             |          |                     |                  |
| Rating in kW / HP   | 2.2 / 3.0                              | Volts (Nom) | 370V     | SI.No               | 1020_4030_100847 |
| Make  | TAG Solar System LLP                   |             | Model No | KISAN UNIVERSAL 3HP |                  |
| Description of the sample and specified requirements as received in data sheet enclosed with customer's Letter. |  |             |          |                     |                  |

**2.0 SUPPLEMENTARY INFORMATION**


|      |   |   |   |      |                   |
|------|---|---|---|------|-------------------|
| 2.1  | Test Method   | As per Ministry of new and Renewable Energy<br>Testing Procedure for Universal Solar Pump Controller (USPC)<br>Annexure-iii of circular no. F. No. 41/3/2018-spv division dated 17.7.2019 |   |      |                   |
| 2.2  | Above sample as received in physically satisfactory condition.  |   |   |      |                   |
| 2.3  | Only the tests requested by the customer have been carried out.   |   |   |      |                   |
| 2.4  | The specified ambient conditions were maintained during the test.   |   |   |      |                   |
| 2.5  | The tests declared in the SI.No (--) are/were sub contracted according to the established procedure of this laboratory.   |   |   |      |                   |
| 2.6  | Reference to the sampling procedure, wherever applicable  |   |   |      | NIL               |
| 2.7  | Supporting documents for the measurements taken and results derived like graphs, tables, sketches and / or photographs as appropriate to test report, if any (to be attached) |   |   |      | Page. No 10 to 19 |
| 2.8  | Deviations from test methods are prescribed in relevant IS / Work instruction if any  |   |   |      | NIL               |
| 2.9  | Measurement of uncertainty of test equipment is considered while testing  |   |   |      |                   |
| 2.10 | "(see remark #)" refers to a remark appended to the report,"(see appended table)" refers to a table appended to the report.   |   |   |      |                   |
|      | Under the test results the following indication (PASS, FAIL, N/A,"----") is marked against suitably.  |   |   |      |                   |
| 2.11 | Test item does meet the requirement   | PASS  | Test item does not meet the requirement     | FAIL |                   |
|      | No Pass / Fail Decision Taken   | "----"  | Test case does not apply to the test object | N/A  |                   |

Tested by

  
B. POOMANIKANDAN  
J.E(Electrical testing)



Approved by

  
D. ANGURAJ  
Engineer(Electrical testing)

TEST REPORT No. : 11 0528

Page 3 of 19

Test Started on: 21.10.2021

Test Completed on:26.10.2021


**3.0 TEST DETAILS**

| SL.NO. | NAME OF THE TEST   | TEST AS PER  |
|--------|--|--|
| 3.1.   | Selection and automatic operation of different solar based agriculture application | As per MNRE Testing Procedure for Universal Solar Pump Controller (USPC) |
| 3.2.   | Total Harmonics Distortion test  | -DO-   |
| 3.3.   | Protection(s) tests  | -DO-   |
| 3.4.   | Remote Monitoring  | -DO-   |
| 3.5.   | Measurement of Dynamic MPPT efficiency   | -DO-   |
| 3.6.   | Measurement of Converter efficiency  | -DO-   |
| 3.7.   | Torque observation on rated motor power  | -DO-   |

**4.0 TEST RESULTS**

| 4 A SELECTION AND AUTOMATIC OPERATION OF DIFFERENT SOLAR BASED AGRICULTURE APPLICATION |   |  |   |  |
|--|---|--|---|--|
| SL.NO.   | NAME OF THE TEST  | SPECIFICATION / TEST REQUIREMENTS  | TEST RESULTS  | REMARKS  |
| 1.   | Application description on screen and selection of applications | LCD screen provided on controller shows various applications which can be selected by keypad using up-down and enter key.  | Provided  |  |
| 2.   | Automatic operation of applications                             | Universal solar Agriculture controller comes with multiple outputs which can be permanently connected to the application by selecting appropriate options of the following application<br>Automatically started <ul style="list-style-type: none"> <li>• Water Pumping</li> <li>• Chaff Cutter</li> <li>• Atta Chakki</li> <li>• Deep fridge/ Cold storage/ Compressor</li> </ul> No manual change over required | Provided,<br><br>No manual change over observed in USPC | At a time, single application operates by the selection among all the connected applications |
| 3.   | Application Specific output (Application specific software)     | USPC should have inbuilt individual application specific software to run the agrarian applications other than pumps  | Provided  | USPC is found to have satisfactory operation for above applications                          |


Tested by



B. POOMANIKANDAN  
J.E(Electrical testing)



Approved by




D. ANGURAJ  
Engineer(Electrical testing)

| SL.NO. | NAME OF THE TEST      | SPECIFICATION / TEST REQUIREMENTS  | TEST RESULTS | REMARKS       |
|--------|-----------------------|--|--------------|---------------|
|        |                       | and output of the controller should be suitable for above mentioned applications |              |               |
| 4.     | Overload torque test. | Up to 150% of rated torque of the connected motor.                               | Satisfactory | Ref Table – 8 |
| 5.     | Constant torque test  | Constant Load given to motor within 100% of rated torque of the motor            | Satisfactory | Ref Table – 7 |
| 6.     | Constant power test   | At variable load i.e. from No load to 150%                                       | Satisfactory | Ref Table – 8 |
| 7.     | Quadratic load test   | Load given to motor within 100% of rated torque of the motor                     | Satisfactory | Ref Table – 2 |
| 8.     | Impact load test      | Load given to motor within 150% of rated torque of the motor                     | Satisfactory | Ref Table – 8 |
| 9.     | Hydraulic load test   | Load given to pump set having rated capacity of the controller.                  | Satisfactory | Ref Table – 2 |


| 4B APPLICATION: SOLAR WATER PUMPING |  |  |                                    |  |
|-------------------------------------|--|--|------------------------------------|--|
| SL.NO.                              | NAME OF THE TEST   | SPECIFICATION / TEST REQUIREMENTS                      | TEST RESULTS                       | REMARKS                                |
| 1.                                  | Input voltage range<br>Minimum- Voc at STC<br>Nominal - Voc at STC<br>Maximum – Voc at STC | 320 V<br>370 V<br>420 V                                | Tested on<br>320,370,420<br>VOC    | Satisfactory<br>Ref Table – 1, 2 and 3 |
| 2.                                  | Ripple and Total Harmonic distortion at output on full load                                | Below 3%   | < 2.98%                            | Satisfactory<br>Ref Table 1, 2 and 3   |
| 3.                                  | Insulation resistance  | 700 M ohm 500 V applied for 1 minute                   | 820 MΩ @ 500V applied for 1 minute | Observed at 28.4°C & 71.7% RH          |
| 4.                                  | Output Voltage (Sine Wave)   | Three phase output with up to 400 V rms pure Sine Wave | Sin Wave<br>CFU 1.49               | Satisfactory                           |

Tested by

  
B. POOMANIKANDAN  
J.E(Electrical testing)




Approved by

  
D. ANGURAJ  
Engineer(Electrical testing)

|       |   |                                |  |  |
|-------|---|--------------------------------|--|--|
| 5.    | Low radiation mode protection                                     | Provided                       | Observed                                   | USPC shutdown at the low radiation if power is not sufficient to drive the particular application and indicates low radiation and Voc value on LCD and operation RANGE for Voc |
| 6.    | Dry run protection  | Provided                       | Observed                                   | Shutdown and Dry run protection on LCD   |
| 7.    | Reverse Polarity Protection                                       | Provided                       | Observed                                   | Satisfactory   |
| 8.    | Short Circuit protection  | Provided                       | Observed                                   | Satisfactory   |
| 9.    | Open circuit protection   | Provided                       | Observed                                   | Satisfactory   |
| 10.   | Remote monitoring   | Provided                       | Built in RMU<br>Observed with data storage | Satisfactory<br>(Ref photograph – 2)   |
| 11.   | Average MPPT tracking efficiency in Hot profile                   | To be measured                 | 99.6%                                      | Hot profile operated with 370 Voc and 3000 Wp array  |
| 12.   | Average MPPT tracking efficiency in Cold Profile                  | To be measured                 | 99.7%                                      | Cold profile operated with 370 Voc and 3000 Wp array   |
| 13.   | Output voltage THD at rated PV                                    | To be measured                 | < 2.01%                                    | Satisfactory   |
| 14.   | Instantaneous output voltage and voltage spikes                   | Sinusoidal & no voltage spikes | Observed                                   | Satisfactory   |
| 15.   | Crest Factor in output at rated PPV                               | 1.6 maximum                    | CFU: 1.49<br>CFI: 1.51                     | Satisfactory<br>Ref Photograph No. 1   |
| 16.   | Efficiency Tests of the Controller at Voc 370 V<br>To be Measured | Controller Efficiency (%)      | MPPT Efficiency (%)                        | Overall charge controller Efficiency (%)<br>Ref Table - .2   |
| 16.1. | At 10% of input power   | 73.26                          | 99.12                                      | 72.62  |
| 16.2. | At 25% of input power   | 86.35                          | 99.43                                      | 85.86  |
| 16.3. | At 50% of input power   | 90.79                          | 99.62                                      | 90.44  |
| 16.4. | At 75% of input power   | 92.46                          | 99.57                                      | 92.06  |
| 16.5. | At 100% of input power  | 93.57                          | 99.57                                      | 93.17  |

Tested by

  
B. POOMANIKANDAN  
J.E(Electrical testing)




Approved by

  
D. ANGURAJ  
Engineer(Electrical testing)

| 4C. APPLICATION: SOLAR BASED CHAFF CUTTER |  |   |                        |   |
|---|--|---|------------------------|---|
| SL.NO.                                    | NAME OF THE TEST   | SPECIFICATION / TEST REQUIREMENTS                     | TEST RESULTS           | REMARKS (REF. TABLE – 4)  |
| 1.  | Input PV voltage range<br>Minimum-Voc at STC<br>Nominal- Voc at STC<br>Maximum-Voc at STC                                | 320 V<br>370 V<br>420 V                               | Observed               | Satisfactory  |
| 2.  | Output voltage waveform  | Sinusoidal at rated conditions 380 to 400 V<br>Ac rms | Observed               | Satisfactory  |
| 3.  | Input PV power range P<br>Nominal  | 3000 Watts STC  | Tested with 3000 Wp    | Satisfactory  |
| 4.  | Motor Rating   | 2 hp, 3 Phase, 50 Hz,<br>6 pole, 910 RPM              | 2 hp                   | Loads as per chaff cutter load  |
| 5.  | Continuous operation started @ power output from array   | To be measured  | 1613 Wp                | Operation starts at 50 Hz above this power with chaff cutter loading  |
| 6.  | Cutter rotation speed for 6 pole type Motor  | To be measured  | 975 RPM at motor pully | Satisfactory  |
| 7.  | DC power in loading condition  | To be measured  | 734-1614 Wp            | Totally depended on loading condition   |
| 8.  | Cutter Operation at different output from 3000 Wp array<br>At 40% Power<br>At 50% Power<br>At 75% Power<br>At 100% Power | To be measured (cutter will not stop functioning)     | Observed               | Above 734 Wp output from array chaff cutter operates satisfactory, else low radiation protection shutdown system and display on LCD |
| 9.  | Production Rate  | kg/ hour  | 560 kg/hour            | Produced 9.3 kg in 1 minute   |
| 10.                                       | Total circuit protection   | Provided  | Observed               | Soft Start up, low radiation protection   |
| 11.                                       | Overload protection  | Provided  | Observed               | Satisfactory  |
| 12.                                       | Short Circuit protection   | Provided  | Observed               | Satisfactory  |
| 13.                                       | Open circuit protection  | Provided  | Observed               | Satisfactory  |
| 14.                                       | Reverse polarity protection  | Provided  | Observed               | Satisfactory  |
| 15.                                       | PV source operating condition during cutter operation  | Operates in constant voltage of PV curve              | Constant               | Satisfactory  |

Tested by

  
B. POOMANIKANDAN  
J.E(Electrical testing)



Approved by

  
D. ANGURAJ  
Engineer(Electrical testing)


TEST REPORT No. : 11 0528

Page 7 of 19

| 4C. APPLICATION: SOLAR BASED CHAFF CUTTER |                     |                                   |                     |                          |
|---|---------------------|-----------------------------------|---------------------|--------------------------|
| SL.NO.                                    | NAME OF THE TEST    | SPECIFICATION / TEST REQUIREMENTS | TEST RESULTS        | REMARKS (REF. TABLE - 4) |
| 16.                                       | Cutter acceleration | Smooth                            | Soft start provided | Satisfactory             |


| 4 D APPLICATION: SOLAR BASED COLD STORAGE/ DEEP FRIDGE/ COMPRESSOR |  |   |                         |   |
|--|--|---|-------------------------|---|
| SL.NO.   | NAME OF THE TEST   | SPECIFICATION / TEST REQUIREMENTS                     | TEST RESULTS            | REMARKS (REF TABLE - 5)   |
| 1.   | Input PV voltage range<br>Minimum-Voc at STC<br>Nominal-Voc at STC<br>Maximum-Voc at STC                                     | 320 V<br>370 V<br>420 V                               | Observed                | Satisfactory  |
| 2.   | Output voltage waveform  | Sinusoidal at rated conditions 380 to 400 V<br>Ac rms | Observed                | Satisfactory  |
| 3.   | Input PV power range P<br>Nominal  | 3000 Watts STC  | Tested with 3000 Wp     | Satisfactory  |
| 4.   | Compressor rating  | Capacity 220 litre,                                   | Volume 220 litre        |   |
| 5.   | Motor rating   | 2.5 hp, 3 Phase, 50 Hz, 4 pole , 1440 RPM             | 2.5 hp                  |   |
| 6.   | Continuous operation started @ power output from array   | To be measured  | 1970 Wp                 | Satisfactory operation starts at 50 Hz above this power with compressor loading   |
| 7.   | Compressor operation at different output from 3000 Wp array<br>At 40% Power<br>At 50% Power<br>At 75% Power<br>At 100% Power | To be measured (Compressor will not stop functioning) | Observed                | Above 739 Wp output from array compressor operates satisfactory, else low radiation protection shutdown system and display on LCD |
| 8.   | Time Required for Air Pressure (0 to 10 bar)   | In minute   | 7 minutes and 20 second | Electrical observation continuous operation found after 739 Wp  |
| 9.   | Total circuit protection   | Provided  | Observed                | Soft Start up, low radiation protection   |
| 10.  | Short Circuit protection   | Provided  | Observed                | Satisfactory  |

Tested by

  
B. POOMANIKANDAN  
J.E(Electrical testing)




Approved by

  
D. ANGURAJ  
Engineer(Electrical testing)

SLFE341/01-00/ 10-21


| <b>4 D APPLICATION: SOLAR BASED COLD STORAGE/ DEEP FRIDGE/ COMPRESSOR</b> |   |  |                      |   |
|---|---|--|----------------------|---|
| <b>SL.NO.</b>   | <b>NAME OF THE TEST</b>   | <b>SPECIFICATION / TEST REQUIREMENTS</b>   | <b>TEST RESULTS</b>  | <b>REMARKS (REF TABLE - 5)</b>  |
| 11.   | Open circuit protection   | Provided   | Observed             | Satisfactory  |
| 12.   | Reverse polarity protection   | Provided   | Observed             | Satisfactory  |
| <b>4 E APPLICATION: SOLAR BASED ATTA CHAKKI</b>                           |   |  |                      |   |
| <b>SL.NO.</b>   | <b>NAME OF THE TEST</b>   | <b>SPECIFICATION / TEST REQUIREMENTS</b>   | <b>TEST RESULTS</b>  | <b>REMARKS (REF TABLE -6)</b>   |
| 1.  | Input PV voltage range<br>Minimum-Voc at STC<br>Nominal-Voc at STC<br>Maximum-Voc at STC                                      | 320 V<br>370 V<br>420 V  | Observed             | Satisfactory  |
| 2.  | Output voltage waveform   | Sinusoidal at rated conditions 380 to 400 V Ac rms   | Observed             | Satisfactory  |
| 3.  | Input PV power range P Nominal  | 3000 Watts   | Tested with 3000 W/p | Satisfactory  |
| 4.  | Atta Chakki type  | 14 inches, open hopper store type, Production rate 14 to 18 kg/hour wheat flour, hopper size 15 to 20 kg | Observed             | 16 kg/hour  |
| 5.  | Atta Chakki motor   | 3 hp, 3 Phase, 50 Hz, 6 pole, 910 RPM  | 3 hp                 | Loads as per Atta Chakki load   |
| 6.  | Continuous operation started @ power output from array  | To be measured   | 2296 Wp              | Operation starts at 50 Hz above this power for full loading   |
| 7.  | Rotation speed  | To be measured   | Motor: 937 RPM       | Satisfactory  |
| 8.  | Atta Chakki operation at different output from 3000 Wp array<br>At 40% Power<br>At 50% Power<br>At 75% Power<br>At 100% Power | To be measured (Atta Chakki will not stop functioning)   | Observed             | Above 708 Wp output from array Atta Chakki operates at full load satisfactory, else below low radiation protection shut downs the system and display on LCD |
| 9.  | Production rate with wheat  | kg/ hour   | 10 kg/hour           | Produced 5.0 kg in 30 minutes   |
| 10.   | Total circuit protection  | Provided   | Observed             | Soft Start up, low radiation protection   |
| 11.   | Overload protection   | Provided   | Observed             | Satisfactory  |

Tested by

  
B. POOMANIKANDAN  
J.E(Electrical testing)



Approved by

  
D. ANGURAJ  
Engineer(Electrical testing)



**SCIENTIFIC AND INDUSTRIAL  
TESTING AND RESEARCH CENTRE  
TESTING LABORATORY**

**Si'Tarc®**

TEST REPORT No. : 11 0528

Page 9 of 19

| 4 D APPLICATION: SOLAR BASED COLD STORAGE/ DEEP FRIDGE/ COMPRESSOR |                             |                                   |              |                         |
|--|-----------------------------|-----------------------------------|--------------|-------------------------|
| SL.NO.   | NAME OF THE TEST            | SPECIFICATION / TEST REQUIREMENTS | TEST RESULTS | REMARKS (REF TABLE - 5) |
| 12.  | Short Circuit protection    | Provided                          | Observed     | Satisfactory            |
| 13.  | Open circuit protection     | Provided                          | Observed     | Satisfactory            |
| 14.  | Reverse polarity protection | Provided                          | Observed     | Satisfactory            |

| DETAILS OF EQUIPMENTS USED AS LOAD |                              |   |           |         |
|------------------------------------|------------------------------|---|-----------|---------|
| S.NO.                              | EQUIPMENT USED               | MODEL                                   | SERIAL NO | REMARKS |
| 1.                                 | Motor and Pump (submersible) | Motor- 3 HP S.S.<br>Pump- 12 stage S.S. | D152522   | 3 Phase |
| 2.                                 | Chaff Cutter                 | 2 HP, 6 pole                            | 103219    | 3 Phase |
| 3.                                 | Compressor                   | 2.5 HP, 4 pole                          | 12634     | 3 Phase |
| 4.                                 | Atta Chakki                  | 3 HP, 6 pole                            | 103219    | 3 Phase |

Tested by



B. POOMANIKANDAN  
J.E(Electrical testing)



Approved by



D.ANGURAJ  
Engineer(Electrical testing)


SI/FE241/01-00/10-21

83&84, AVARAMPALAYAM ROAD, K.R. PURAM P.O., COIMBATORE - 641 006. ☎ : 91-0422 - 2560473

☎ : 94875 80473 E-Mail : sitarcinfo@sitarc.com, Website : www.sitarc.com

| TABLE 1 |                           | CONVERTER EFFICIENCY AT MINIMUM VOLTAGE (TESTED AT VOLTAGE AT 320 Voc) |        |        |        |        |
|---------|---------------------------|--|--------|--------|--------|--------|
| S.NO.   | INPUT POWER %             | 10   | 25     | 50     | 75     | 100    |
| 1.      | Udc-1-Total               | 293.4  | 258.2  | 251.9  | 257.5  | 283.5  |
| 2.      | Idc-1-Total               | 0.82   | 2.88   | 5.81   | 8.56   | 9.55   |
| 3.      | P-1-Total                 | 241  | 738    | 1462   | 2204   | 2706   |
| 4.      | FreqU-Total (Hz)          | 12.88  | 20.36  | 32.71  | 39.95  | 43.16  |
| 5.      | Uthd-2-Total              | -  | 1.60   | 1.33   | 1.30   | 1.26   |
| 6.      | lthd-2-Total              | -  | 1.46   | 1.62   | 2.76   | 1.67   |
| 7.      | Uthd-3-Total              | -  | 1.79   | 1.40   | 1.45   | 1.40   |
| 8.      | lthd-3-Total              | -  | 2.54   | 1.62   | 2.19   | 1.39   |
| 9.      | Uthd-4-Total              | -  | 1.88   | 1.43   | 1.48   | 1.47   |
| 10.     | lthd-4-Total              | -  | 2.47   | 2.35   | 2.39   | 1.84   |
| 11.     | Urms-SigmaA-Total         | 105.95   | 162.8  | 265.9  | 322.16 | 348.78 |
| 12.     | Irms-SigmaA-Total         | 4.00   | 4.20   | 5.00   | 5.50   | 6.00   |
| 13.     | P-SigmaA-Total (W)        | 180  | 650    | 1340   | 2040   | 2520   |
| 14.     | PF-SigmaA-Total           | 0.2456   | 0.5445 | 0.5824 | 0.6595 | 0.6973 |
| 15.     | S-SigmaA-Total (VA)       | 730  | 1190   | 2300   | 3090   | 3610   |
| 16.     | Q-SigmaA-Total (VA)       | 710  | 1000   | 1870   | 2330   | 2600   |
| 17.     | Controller efficiency (%) | 74.69  | 88.08  | 91.66  | 92.56  | 93.13  |
| 18.     | Mppt efficiency (%)       | 99.21  | 99.18  | 99.24  | 99.51  | 99.57  |
| 19.     | Overall system efficiency | 74.10  | 87.35  | 90.96  | 92.11  | 93.10  |

Tested by

  
B. POOMANIKANDAN  
J.E(Electrical testing)



Approved by

  
D. ANGURAJ  
Engineer(Electrical testing)

| <b>TABLE 2</b> |                           | <b>CONVERTER EFFICIENCY AT NOMINAL VOLTAGE (TESTED AT VOLTAGE AT 370 Voc)</b> |           |           |           |            |
|----------------|---------------------------|---|-----------|-----------|-----------|------------|
| <b>S.NO.</b>   | <b>LOAD %</b>             | <b>10</b>   | <b>25</b> | <b>50</b> | <b>75</b> | <b>100</b> |
| 1.             | Udc-1-Total               | 313.23  | 281.1     | 298.3     | 285.1     | 307.1      |
| 2.             | Idc-1-Total               | 0.83  | 2.59      | 4.96      | 7.63      | 9.38       |
| 3.             | P-1-Total                 | 273   | 718       | 1476      | 2174      | 2939       |
| 4.             | FreqU-Total (Hz)          | 16.04   | 17.82     | 31.02     | 38.38     | 43.09      |
| 5.             | Uthd-2-Total              | -   | 1.71      | 1.25      | 1.28      | 1.30       |
| 6.             | lthd-2-Total              | -   | 2.46      | 1.67      | 1.95      | 0.63       |
| 7.             | Uthd-3-Total              | -   | 1.89      | 1.35      | 1.40      | 1.46       |
| 8.             | lthd-3-Total              | -   | 2.10      | 1.41      | 0.81      | 1.36       |
| 9.             | Uthd-4-Total              | -   | 2.01      | 1.36      | 1.39      | 1.47       |
| 10.            | lthd-4-Total              | -   | 2.98      | 1.61      | 1.46      | 1.42       |
| 11.            | Urms-SigmaA-Total         | 133.42  | 152.40    | 269.90    | 334.79    | 371.20     |
| 12.            | Irms-SigmaA-Total         | 4.2   | 4.7       | 5.6       | 6.1       | 6.6        |
| 13.            | P-SigmaA-Total (W)        | 200   | 620       | 1340      | 2010      | 2750       |
| 14.            | PF-SigmaA-Total           | 0.2089  | 0.4988    | 0.5134    | 0.5644    | 0.6439     |
| 15.            | S-SigmaA-Total (VA)       | 970   | 1240      | 2620      | 3550      | 4270       |
| 16.            | Q-SigmaA-Total (VA)       | 950   | 1080      | 2250      | 2940      | 3290       |
| 17.            | Controller efficiency (%) | 73.26   | 86.35     | 9.79      | 92.46     | 93.57      |
| 18.            | Mppt efficiency (%)       | 99.12   | 99.43     | 99.62     | 99.57     | 99.57      |
| 19.            | Overall system efficiency | 72.26   | 85.86     | 90.44     | 92.06     | 93.17      |

Tested by

*B.P.K.*

B. POOMANIKANDAN  
J.E(Electrical testing)




Approved by

*D.A.*

D. ANGURAJ  
Engineer(Electrical testing)

| <b>TABLE 3 CONVERTER EFFICIENCY AT MAXIMUM VOLTAGE (TESTED AT VOLTAGE AT 420 Voc)</b> |                           |           |           |           |           |            |
|---|---------------------------|-----------|-----------|-----------|-----------|------------|
| <b>S.NO.</b>  | <b>LOAD %</b>             | <b>10</b> | <b>25</b> | <b>50</b> | <b>75</b> | <b>100</b> |
| 20.   | Udc-1-Total               | 339.90    | 328.99    | 331.40    | 334.13    | 361.54     |
| 21.   | Idc-1-Total               | 0.87      | 2.29      | 4.43      | 6.61      | 8.00       |
| 22.   | P-1-Total                 | 296       | 730       | 1466      | 2205      | 2889       |
| 23.   | FreqU-Total (Hz)          | 18.46     | 19.92     | 30.00     | 39.49     | 45.05      |
| 24.   | Uthd-2-Total              | -         | 1.83      | 1.29      | 1.27      | 1.25       |
| 25.   | lthd-2-Total              | -         | 2.73      | 2.18      | 1.22      | 1.01       |
| 26.   | Uthd-3-Total              | -         | 2.04      | 1.37      | 1.39      | 1.46       |
| 27.   | lthd-3-Total              | -         | 2.57      | 2.59      | 2.09      | 1.24       |
| 28.   | Uthd-4-Total              | -         | 2.20      | 1.42      | 1.40      | 1.49       |
| 29.   | lthd-4-Total              | -         | 2.30      | 1.65      | 1.82      | 1.79       |
| 30.   | Urms-SigmaA-Total         | 153.79    | 143.23    | 259.43    | 341.19    | 387.56     |
| 31.   | Irms-SigmaA-Total         | 4.40      | 4.60      | 5.50      | 6.00      | 6.50       |
| 32.   | P-SigmaA-Total (W)        | 230       | 620       | 1340      | 2030      | 2750       |
| 33.   | PF-SigmaA-Total           | 0.2006    | 0.5480    | 0.54005   | 0.5685    | 0.6254     |
| 34.   | S-SigmaA-Total (VA)       | 1100      | 1140      | 2490      | 3570      | 4390       |
| 35.   | Q-SigmaA-Total (VA)       | 140       | 960       | 2080      | 2940      | 3440       |
| 36.   | Controller efficiency (%) | 77.70     | 84.93     | 91.41     | 92.06     | 95.19      |
| 37.   | Mppt efficiency (%)       | 99.10     | 99.18     | 99.19     | 99.47     | 99.52      |
| 38.   | Overall system efficiency | 77.00     | 84.24     | 90.66     | 91.58     | 94.73      |

Tested by



**B. POOMANIKANDAN**  
J.E(Electrical testing)



Approved by



**D. ANGURAJ**  
Engineer(Electrical testing)

| TABLE 4 |                           | CHAFF CUTTER OPERATION |       |        |        |        |        |
|---------|---------------------------|------------------------|-------|--------|--------|--------|--------|
| S.NO.   | POWER %                   | 25                     | 30    | 40     | 50     | 75     | 100    |
| 1.      | Udc-1-Total               | 293.3                  | 300.2 | 290.5  | 288.1  | 344.3  | 352.5  |
| 2.      | Idc-1-Total               | 2.50                   | 2.95  | 4.03   | 5.06   | 4.69   | 4.58   |
| 3.      | P-1-Total                 | 734                    | 887   | 1170   | 1457   | 1613   | 1614   |
| 4.      | FreqU-Total (Hz)          | 31.90                  | 36.03 | 42.69  | 47.31  | 50.49  | 50.50  |
| 5.      | Uthd-2-Total              | 2.38                   | 2.28  | 2.18   | 1.96   | 1.92   | 1.91   |
| 6.      | lthd-2-Total              | 2.35                   | 2.76  | 2.44   | 2.42   | 1.92   | 2.88   |
| 7.      | Uthd-3-Total              | 2.56                   | 2.34  | 2.24   | 2.00   | 1.95   | 1.95   |
| 8.      | lthd-3-Total              | 2.54                   | 2.99  | 2.50   | 2.86   | 2.14   | 2.69   |
| 9.      | Uthd-4-Total              | 2.69                   | 2.34  | 2.57   | 2.39   | 2.38   | 2.38   |
| 10.     | lthd-4-Total              | 2.73                   | 2.38  | 2.46   | 2.51   | 2.29   | 2.73   |
| 11.     | Urms-SigmaA-Total         | 251.0                  | 283.1 | 337.6  | 370.9  | 405.6  | 405.7  |
| 12.     | Irms-SigmaA-Total         | 2.62                   | 2.86  | 3.0    | 3.2    | 3.3    | 3.3    |
| 13.     | P-SigmaA-Total (W)        | 660                    | 810   | 1050   | 1340   | 1470   | 1460   |
| 14.     | PF-SigmaA-Total           | -                      | -     | 0.5892 | 0.6463 | 0.6327 | 0.6313 |
| 15.     | S-SigmaA-Total (VA)       | -                      | -     | 1780   | 2080   | 2230   | 2320   |
| 16.     | Q-SigmaA-Total (VA)       | -                      | -     | 1450   | 1630   | 1820   | 1820   |
| 17.     | Controllor efficiency (%) | 89.92                  | 91.32 | 89.74  | 91.97  | 92.37  | 93.56  |
| 18.     | Speed in rpm              | 596                    | 693   | 746    | 825    | 975    | 974    |
| 19.     | Torque in Nm              | 7.862                  | 8.861 | 10.03  | 10.72  | 12.01  | 12.17  |

Tested by

*B.P.J.*

B. POOMANIKANDAN  
J.E(Electrical testing)




Approved by

*D.A.*

D.ANGURAJ  
Engineer(Electrical testing)


| TABLE 5 |                           | COMPRESSOR OPERATION |        |        |        |        |        |
|---------|---------------------------|----------------------|--------|--------|--------|--------|--------|
| S.NO.   | POWER %                   | 25                   | 30     | 40     | 50     | 75     | 100    |
| 1.      | Udc-1-Total               | 300.4                | 285.9  | 295.5  | 300.8  | 332.1  | 346.7  |
| 2.      | Idc-1-Total               | 2.46                 | 3.05   | 3.99   | 4.91   | 5.93   | 5.72   |
| 3.      | P-1-Total                 | 739                  | 870    | 1177   | 1478   | 1970   | 1984   |
| 4.      | FreqU-Total (Hz)          | 27.46                | 3034   | 36.62  | 42.32  | 50.48  | 50.44  |
| 5.      | Uthd-2-Total              | 1.85                 | 2.09   | 2.00   | 1.86   | 1.76   | 1.76   |
| 6.      | lthd-2-Total              | 2.22                 | 2.80   | 2.47   | 2.85   | 2.49   | 2.31   |
| 7.      | Uthd-3-Total              | 1.88                 | 2.03   | 1.98   | 1.59   | 1.73   | 1.77   |
| 8.      | lthd-3-Total              | 2.22                 | 2.91   | 2.56   | 2.35   | 2.33   | 2.44   |
| 9.      | Uthd-4-Total              | 2.07                 | 2.42   | 2.32   | 2.02   | 2.18   | 2.18   |
| 10.     | lthd-4-Total              | 2.68                 | 2.65   | 2.80   | 2.68   | 2.33   | 2.82   |
| 11.     | Urms-SigmaA-Total         | 215.5                | 237.2  | 286.8  | 329.1  | 404.0  | 403.9  |
| 12.     | Irms-SigmaA-Total         | 2.6                  | 3.1    | 3.3    | 3.5    | 3.8    | 3.8    |
| 13.     | P-SigmaA-Total (W)        | 670                  | 800    | 1090   | 1390   | 1800   | 1830   |
| 14.     | PF-SigmaA-Total           | -                    | 0.6299 | 0.6603 | 0.6939 | 0.6830 | 0.6887 |
| 15.     | S-SigmaA-Total (VA)       | -                    | 1260   | 1650   | 2000   | 2640   | 2660   |
| 16.     | Q-SigmaA-Total (VA)       | -                    | 990    | 1260   | 1480   | 1930   | 1970   |
| 17.     | Controller efficiency (%) | 90.66                | 91.95  | 92.61  | 94.05  | 91.37  | 93.25  |

Tested by

  
B. POOMANIKANDAN  
J.E(Electrical testing)



Approved by

  
D. ANGURAJ  
Engineer(Electrical testing)

**SCIENTIFIC AND INDUSTRIAL  
TESTING AND RESEARCH CENTRE  
TESTING LABORATORY**


**Si'Tarc®**

TEST REPORT No. : 11 0528

Page 15 of 19


| TABLE 6 |                           | ATTA CHAKKI OPERATION |        |        |        |        |        |
|---------|---------------------------|-----------------------|--------|--------|--------|--------|--------|
| S.NO.   | POWER %                   | 25                    | 30     | 40     | 50     | 75     | 100    |
| 1.      | Udc-1-Total               | 275.4                 | 299.9  | 293.4  | 290.8  | 292.5  | 341.0  |
| 2.      | Idc-1-Total               | 2.57                  | 2.96   | 4.00   | 5.04   | 7.51   | 6.73   |
| 3.      | P-1-Total                 | 708                   | 888    | 1176   | 1462   | 2199   | 2296   |
| 4.      | FreqU-Total (Hz)          | 24.83                 | 28.51  | 31.01  | 35.61  | 46.26  | 50.11  |
| 5.      | Uthd-2-Total              | 1.30                  | 1.26   | 1.02   | 1.06   | 1.20   | 1.34   |
| 6.      | lthd-2-Total              | 2.64                  | 2.88   | 2.40   | 2.93   | 2.73   | 1.96   |
| 7.      | Uthd-3-Total              | 1.64                  | 1.26   | 0.96   | 0.88   | 0.87   | 1.09   |
| 8.      | lthd-3-Total              | 2.04                  | 2.61   | 2.27   | 1.42   | 1.68   | 2.33   |
| 9.      | Uthd-4-Total              | 1.66                  | 1.58   | 1.29   | 1.23   | 1.46   | 1.56   |
| 10.     | lthd-4-Total              | 2.81                  | 2.91   | 1.88   | 2.73   | 1.36   | 2.09   |
| 11.     | Urms-SigmaA-Total         | 179.6                 | 207.2  | 222.2  | 256.6  | 331.5  | 361.3  |
| 12.     | Irms-SigmaA-Total         | 3.0                   | 3.2    | 3.8    | 4.0    | 4.7    | 4.5    |
| 13.     | P-SigmaA-Total (W)        | 660                   | 830    | 1100   | 1370   | 2090   | 2150   |
| 14.     | PF-SigmaA-Total           | 0.7029                | 0.7093 | 0.7581 | 0.7662 | 0.7776 | 0.7613 |
| 15.     | S-SigmaA-Total (VA)       | 940                   | 1160   | 1450   | 1790   | 2680   | 2820   |
| 16.     | Q-SigmaA-Total (VA)       | 680                   | 830    | 970    | 1170   | 1710   | 1850   |
| 17.     | Controller efficiency (%) | 93.22                 | 93.47  | 93.54  | 93.71  | 95.04  | 93.64  |
| 18.     | Speed in rpm              | 441                   | 528    | 562    | 654    | 851    | 937    |
| 19.     | Torque in Nm              | 10.19                 | 11.38  | 14.06  | 15.48  | 18.27  | 17.83  |

Tested by

  
B. POOMANIKANDAN  
J.E(Electrical testing)



Approved by

  
D. ANGURAJ  
Engineer(Electrical testing)


SLEF341/01-00/10-21

83&84, AVARAMPALAYAM ROAD, K.R. PURAM P.O., COIMBATORE - 641 006. © : 91-0422 - 2560473

☎ : 94875 80473 E-Mail : sitarcinfo@sitarc.com, Website : www.sitarc.com

| TABLE 7 |                           | TORQUE OBSERVATION ON 3 HP MOTOR WITH DYNAMOMETER AS LOAD |        |        |        |        |        |
|---------|---------------------------|---|--------|--------|--------|--------|--------|
| S.NO.   | POWER %                   | 25  | 30     | 40     | 50     | 75     | 100    |
| 1.      | Udc-1-Total               | 275.4   | 290.3  | 303.5  | 300    | 294.7  | 340.8  |
| 2.      | Idc-1-Total               | 2.57  | 3.02   | 3.90   | 4.92   | 7.47   | 6.78   |
| 3.      | P-1-Total                 | 708   | 887    | 1183   | 1477   | 2204   | 2311   |
| 4.      | FreqU-4-Total (Hz)        | 24.70   | 28.34  | 31.01  | 35.86  | 46.10  | 50.26  |
| 5.      | Uthd-2-Total              | 1.33  | 1.20   | 1.12   | 0.98   | 1.22   | 1.37   |
| 6.      | Ithd-2-Total              | 1.39  | 2.77   | 2.85   | 2.89   | 1.10   | 1.73   |
| 7.      | Uthd-3-Total              | 1.51  | 1.26   | 0.99   | 1.05   | 1.07   | 1.09   |
| 8.      | Ithd-3-Total              | 2.77  | 2.65   | 2.88   | 2.13   | 1.33   | 1.92   |
| 9.      | Uthd-4-Total              | 1.66  | 1.57   | 1.37   | 1.30   | 1.54   | 1.55   |
| 10.     | Ithd-4-Total              | 2.52  | 1.25   | 1.78   | 2.13   | 1.14   | 2.49   |
| 11.     | Urms-SigmaA-Total         | 179.9   | 204.7  | 224.0  | 257.8  | 332.1  | 361.3  |
| 12.     | Irms-SigmaA-Total         | 2.0   | 3.2    | 3.8    | 4.1    | 4.7    | 4.6    |
| 13.     | P-SigmaA-Total (W)        | 650   | 800    | 1120   | 1390   | 2080   | 2180   |
| 14.     | PF-SigmaA-Total           | -   | 0.7085 | 0.7633 | 0.7686 | 0.7767 | 0.7665 |
| 15.     | S-SigmaA-Total (VA)       | 630   | 1130   | 1460   | 1810   | 2680   | 2850   |
| 16.     | Q-SigmaA-Total (VA)       | 690   | 830    | 970    | 1180   | 1720   | 1860   |
| 17.     | Controller efficiency (%) | 91.81   | 90.19  | 94.67  | 94.11  | 94.37  | 94.33  |
| 18.     | RPM                       | 439   | 525    | 567    | 657    | 851    | 934    |
| 19.     | Torque in Nm              | 10.12   | 11.41  | 14.09  | 15.50  | 18.26  | 17.12  |


Tested by



B. POOMANIKANDAN  
J.E(Electrical testing)



Approved by



D. ANGURAJ  
Engineer(Electrical testing)



**SCIENTIFIC AND INDUSTRIAL  
TESTING AND RESEARCH CENTRE  
TESTING LABORATORY**


**Si'Tarc<sup>®</sup>**

TEST REPORT No. : 11 0528

Page 17 of 19


| TABLE 8 |                           | TORQUE OBSERVATION ON 3 HP MOTOR WITH DYNAMOMETER AS LOAD |       |        |        |        |        |
|---------|---------------------------|---|-------|--------|--------|--------|--------|
| S.NO.   | LOAD %                    | 25  | 50    | 75     | 100    | 125    | 150    |
| 1.      | Udc-1-Total               | 362.9   | 357.5 | 350.0  | 339.4  | 322.5  | 321.1  |
| 2.      | Idc-1-Total               | 1.96  | 3.44  | 5.13   | 6.97   | 8.72   | 8.75   |
| 3.      | P-1-Total                 | 710   | 1229  | 1796   | 2365   | 2813   | 2829   |
| 4.      | FreqU-4-Total (Hz)        | 50.45   | 50.43 | 50.44  | 50.43  | 50.44  | 46.18  |
| 5.      | Uthd-2-Total              | -   | 1.95  | 1.69   | 1.35   | 1.16   | 1.72   |
| 6.      | lthd-2-Total              | -   | 1.60  | 2.88   | 2.11   | 1.98   | 1.38   |
| 7.      | Uthd-3-Total              | -   | 2.0   | 1.50   | 1.10   | 0.88   | 1.09   |
| 8.      | lthd-3-Total              | -   | 1.87  | 2.45   | 2.87   | 2.20   | 2.03   |
| 9.      | Uthd-4-Total              | -   | 2.42  | 2.02   | 1.55   | 1.33   | 1.84   |
| 10.     | lthd-4-Total              | -   | 2.71  | 2.70   | 1.88   | 1.14   | 1.92   |
| 11.     | Urms-SigmaA-Total         | 382.3   | 379.3 | 376.8  | 374.6  | 373.1  | 347.9  |
| 12.     | Irms-SigmaA-Total         | 1.7   | 2.4   | 3.6    | 4.5    | 5.3    | 6.2    |
| 13.     | P-SigmaA-Total (W)        | 640   | 1130  | 1680   | 2250   | 2660   | 2708   |
| 14.     | PF-SigmaA-Total           | -   | -     | 0.7142 | 0.7709 | 0.7778 | 0.7820 |
| 15.     | S-SigmaA-Total (VA)       | -   | -     | 2350   | 2920   | 3410   | 3520   |
| 16.     | Q-SigmaA-Total (VA)       | -   | -     | 1670   | 1900   | 2170   | 2010   |
| 17.     | Controller efficiency (%) | 90.14   | 91.94 | 93.54  | 95.14  | 94.56  | 95.72  |
| 18.     | RPM                       | 995   | 979   | 960    | 936    | 918    | 881    |
| 19.     | Torque in Nm              | 4.509   | 9.056 | 13.68  | 18.16  | 22.53  | 27.18  |

Tested by

  
B. POOMANIKANDAN  
J.E.(Electrical testing)



Approved by

  
D. ANGURAJ  
Engineer(Electrical testing)

SLFE341/01-00/ 10-21


83&84, AVARAMPALAYAM ROAD, K.R. PURAM P.O., COIMBATORE - 641 006. ☎ : 91-0422 - 2560473

☎ : 94875 80473 E-Mail : sitarcinfo@sitarc.com, Website : www.sitarc.com

**PHOTGRAPHS - 1**

**OUTPUT WAVE OF USPC AT DIFFERENT  
RADIATION / POWER**


**RADIATION 250 W/m<sup>2</sup>**




**RADIATION 450 W/m<sup>2</sup>**



**RADIATION 650 W/m<sup>2</sup>**



**RADIATION 950 W/m<sup>2</sup>**



Tested by

*B. Poomanikandan*  
B. POOMANIKANDAN  
J.E(Electrical testing)



Approved by

*D. Anguraj*  
D. ANGURAJ  
Engineer(Electrical testing)


PHOTOGRAPHS - 2

FRONT VIEW




VISUAL INSPECTION OF USPC

NAME PLATE OF THE CONTROLLER



DATA STORAGE PROVISION



- End of the Report -

Tested by

B. POOMANIKANDAN  
J.E(Electrical testing)



Approved by

D. ANGURAJ  
Engineer(Electrical testing)